

Equipment Install -NYSTA Exit 37

**Liverpool, Onondaga County, NY, NYSTA-MP283.95
I-90 to AT&T, NYSTA Exit 37 Cell Tower**

CONTRACTOR:

- Infraservices: Syracuse, NY
- Project Manager: Darrell Paulson

POINT OF CONTACT:

- Darrell Paulson: (315)-679-3145
- Mike Judson: (978)-436-0429

CONSTRUCTION MANAGER:

- Mike Judson: (978)-436-0429

LOCATION:

- Mile Post 283.95

TRAFFIC CONTROL:

- N/A-All equipment to be offloaded and used inside cell tower compound. No street closures are required.

SCOPE OF WORK:

GROUND SCOPE OF WORK:

- INSTALL NEW WUC AND 30KW DIESEL GENERATOR W/ 145 GALLON BELLY TANK ON PROPOSED STEEL PLATFORM AT GRADE.
- INSTALL NEW CABLE ICE BRIDGE FROM WUC TO EXISTING TOWER.
- INSTALL NEW 200A 120/240V UTILITY SERVICE FROM EXISTING METER BOARD TO NEW WUC.
- INSTALL NEW CONDUIT FOR BACKHAUL SERVICE TO WUC FROM EXISTING TELCO DEMARC.
- INSTALL (3) NEW FIBER MANAGEMENT BOXES.

ANTENNA LEVEL SCOPE OF WORK:

- INSTALL (12) NEW PANEL ANTENNAS ON NEW ANTENNA MOUNTS ON EXISTING TOWER.
- INSTALL (12) REMOTE RADIO UNITS (RRU'S).
- INSTALL (3) DC9 SURGE SUPPRESSOR UNITS.
- INSTALL (3) FIBER AND (8) DC TRUNK CABLES FROM WUC TO ANTENNAS.
- INSTALL (1) SITEPRO 1 ANTENNA QUAD MOUNT FRAME

GENERAL NOTES:

- Underground locating will be contacted 48 hours prior to the start of work and no work will be performed prior to existing utility stakeout.
- Trenches and pits to be backfilled with suitable excavated material. All backfill to be mechanically tamped in 6" lifts. Unsuitable material to be removed from the site. A minimum of 3" of topsoil to be installed along with suitable grass seed mixture, straw mulch and fertilizer. All other areas disturbed during construction shall be graded, top soiled and seeded similar to the above procedure.

CONDUIT OPEN CUT INSTALLATION NOTES:

- All trenching, excavation and backfill shall conform to the requirements of the local Governing Authority.
- Refer to NYSDOT Standard Specifications for Backfill Material and compaction densities.
- Slope as required to maintain stability of trench sidewall, or provide sheeting and shoring to ensure safety of personnel, a protection of adjacent facilities.
- Trench Excavations greater than four feet (4') in depth shall be adequately shored per OSHA Standards.
- Initial Backfill: the depth of the initial backfill shall be from the top of the bedding layer to four inches (4") above the crown of the conduit. Initial backfill to be clean Pea Stone or #1 crushed stone
- Final Backfill: The depth of the final backfill shall be from the top of the initial backfill to the top of the rough grade.
- Excavated material shown in the typical sections are rough approximations only. The contractor is responsible for verifying and calculating the final quantities.
- Cable Marking tape shall be placed 18" minimum over all direct buried conduits.
- The Contractor shall patch and repair damaged surfaces to a condition greater than or equal to conditions prior to construction activities.
- Conduit to be 4" PVC Bell and Spigot conduit, SCH-40.