



NEW YORK STATE
THRUWAY AUTHORITY . CANAL CORPORATION



APPLICATION FOR **CONSTRUCTION PERMIT**

☐ ORIGINAL ☐ RENEWAL ☐ CHANGE NOTICE ☒ CONSTRUCTION PERMIT

Project Description: THERE ARE 3 PAGES TO THIS PERMIT PLEASE BE SURE TO READ ALL PAGES AND COMPLY WITH ALL CONDITIONS.

Verizon installing (3) antenna mounts; (6) panel antennas; (3) RRH/antenna units; (6) Dual band RRH units; (2) 6x12 hybrid cables; (1) 3x6 hybrid cable; (2) OVPs on new monopole installing (2) OVPs on proposed H frame at grade; (1) diesel generator on concrete pad; equipment cabinets on concrete slab at grade within an existing fenced compound.

Contract Number:

Letting Date:

Construction Start Date:

Construction End Date:

TYPE OF WORK:	☒ ERECTION	☒ ALTERATION	☒ IMPROVEMENT	☐ ENLARGEMENT
	☒ CONSTRUCTION	☐ DEMOLITION	☐ RELOCATION	☐ REPAIRS
ELEMENTS INVOLVED	☒ STRUCTURAL	☐ PLUMBING	☒ ELECTRICAL	☒ MECHANICAL
	☐ FUEL GAS	☐ ENERGY	☐ FIRE PROTECTION	

Building Use/Occupancy:

Site Use/Description: Interchange - Behind T3637

Project Size: 0 SqFt

Project Cost: \$0.00

Address:

GIS Coordinates: 0

Applicant Signature:

Jackie Donahue

Address: PHOENIX TOWERS INTERNATIONAL 999 YOMOTO ROAD, SUIT 100 BOCO RATON,

FLORIDA

Prepared By: JACKIE DONAHUE

Phone No.

570-362-1147

CONSTRUCTION PERMIT

CONSTRUCTION PERMIT NO. CP2025-076

Project complies and is in conformance with applicable provisions of Uniform Code? ☒ YES ☐ NO

Inspection Agency: NYSTA / NYSCC Person in Charge:

Final Inspection Needed? ☒ YES ☐ NO Authorization to Proceed Granted Date: **October 16, 2025**

Period for Which Permit is Granted From: **October 16, 2025** To: **October 16, 2026**

Permit Not Required:

Permit Denied:

ISSUING OFFICIAL: Joshua Stagnitti

SIGNATURE: _____

DATE: 10/14/2025

ACP01-2 (01/03)

CONSTRUCTION PERMIT CONDITIONS

CONSTRUCTION PERMIT No: CP2025-076

THIS CONSTRUCTION PERMIT IS ISSUED FOR:

THERE ARE 3 PAGES TO THIS PERMIT PLEASE BE SURE TO READ ALL PAGES AND COMPLY WITH ALL CONDITIONS. Verizon

installing (3) antenna mounts; (6) panel antennas; (3) RRH/antenna units; (6) Dual band RRH units; (2) 6x12 hybrid cables; (1) 3x6 hybrid cable; (2) OVPs on new monopole installing (2) OVPs on proposed H frame at grade; (1) diesel generator on concrete pad; equipment cabinets on concrete slab at grade within an existing fenced compound.

AND IS SUBJECT TO THE FOLLOWING CONDITIONS:

- 1: That two sets of constructions plans, bearing the original seal and signature of NYS Professional Engineer or Registered Architect, as provided for in Sections 7307 and 7209 of the NYS Education Law and Section 448.7(b)(6) of 19 NYCRR be provided.
- 2: That copies of Construction Inspection Reports completed for/during this project be provided to this office in a timely manner.
- 3: That all electrical work comply with NFPA 70 and the NYS Uniform Fire Prevention and Building Code and be inspected by an approved Electrical Inspection Agency and a copy of the final electrical inspection be provided.
- 4: That this office be provided with all change orders subject to this project for review and approval prior to their implementation.
- 5: That this office be notified of near completion or completion so that a final inspection may be conducted in a timely manner.
- 6: You are to notify the Bureau of Facilities and Code Compliance (in the Department of Maintenance Engineering) at the New York State Thruway Authority of commencement of work under this Permit and prior to the start of the following construction stages in order to schedule required inspections.
 - ☒ 1. Footing before pouring concrete.
 - ☐ 2. Foundation before backfill.
 - ☐ 3. Framing before enclosing.
 - ☐ 4. Electrical before enclosing.
 - ☐ 5. Insulation before enclosing.
 - ☐ 6. Plumbing before enclosing.
 - ☐ 7. Heating, Ventilation, Air Conditioning before enclosing.
 - ☐ 8. Septic System and Well.
 - ☒ 9. Final Completion.
- 7: It is also required that timely notice be given to the Bureau of Facilities and Code Compliance of the readiness of construction for all test which the Uniform Code requires for inspection and approval. Copies of all tests and their certification of approval are required to be submitted to the NYSTA prior to final inspections.
- 8: Authority having jurisdiction for the issuance of a Construction Permit is the NYS Thruway Authority. A

Construction Permit is required for this project and will be issued upon satisfaction of sufficient information to determine compliance with the NYS Uniform Fire Prevention and Building Code, the ADA, and the NYS Public Building Law. No construction may commence until a valid Permit is issued by this office.

9: That Special Inspections to be performed in accordance with Part 1221 Chapters 9 and 17, (Building Code), and Part 1223 Chapter 5 (Mechanical Code), of 19 NYCRR (the NYS Uniform Fire Prevention and Building Code).

10: Concrete Notes- Note 2- Compressive strength of concrete reports shall be submitted to NYSTA Code. Reports are required for all concrete pours regardless of amount of concrete poured. They are required for confirmation that concrete meets the required 4500psi requirement and for final code compliance certificate.

11: Third party steel reinforcement inspection is required and reports shall be submitted to NYSTA Code. These reports are required for final code compliance certificate.

12: All welding requires to be inspected by a third party. reports shall be submitted to NYSTA Code. These reports are required for final code compliance certificate.

13: Concrete slump reports shall be submitted to NYSTA Code. These reports are required for final code compliance certificate.

14: Ground testing reports shall be submitted to NYSTA Code. These reports are required for final code compliance certificate.

15: EOR shall sign off confirming all work has been completed by submitted plans. A post construction inspection shall be conducted, and a copy of the final report shall be provided. All engineer paperwork shall be signed, stamped and include their license registration expiration date.

16: For any/all items not associated with the 2020 New York State Building Codes or electrical work please reach out to the following:

Jackie Danahue
Sales Manager TMO & NYSTA
Phonex Tower International
999 Yamato Road, Suite 100
Boca Raton, FL 33431
jdonahue@phoenixintl.com
570.362.1147-M

